

P.O. Box 370 • 302 North Erickson/Industrial Park • Roland, IA 50236 Toll Free: (888) 54 HOIST • Telephone: (515) 388-4118 • Fax: (515) 388-4340

Web: www.mathoist.com • Email: mathoist@mathoist.com

SPECIFICATIONS: Mat Hoist® Storage System Model 1000 "Superhoist"

1.0 GENERAL

- **A.** Stores up to **three** 45' x 45' mats.
- **B.** Three cable balanced lift system.
- C. 17,500 lbs. load test for safety.
- **D.** Fifteen-year manufacturer's warranty.
- E. Manual lowering override brake

1.1 PRODUCT INTRODUCTION

- A. "Load tested" direct drive motor operated mat storage system with Fifteen-year warranty. (No exceptions)
- **B.** Twenty-foot long universal I-Beam frame provides adaptability to structural steel.
- **C.** Four movable unit clamps with eight grade B-7 3/4" x 18" supporting rods.

1.2 WORK SPECIFIED ELSEWHERE

A. Electrical work. B. Added structural steel. C. Field painting. D. Wrestling mat. E. Installation 1.3 SUBMITTALS UPON REQUEST

- A. Mat Hoist® AutoCAD drawings showing storage system, mounting brackets and wiring diagrams.
- **B.** Documented proof of a load test for safety.

2.0 PRODUCT SPECIFICATIONS

- **2.1** Ceiling or wall supported mat storage system shall be the **Mat Hoist® Model 1000 "Superhoist"** as manufactured by N.G.E. Inc., P.O. Box 370, 302 N. Erickson, Industrial Park (northeast), Roland, IA 50236, (515) 388-4118 and FAX (515) 388-4340, **website: www.mathoist.com**, having these features:
 - **A. MAT HOIST**: Mat storage hoist shall be a twenty-foot long lift/lower I-beam frame. Unit must have a highly efficient hollow bored helical gear direct drive (2" diameter) solid keyed shaft. System must have a forty-foot long load bar and one (1) top one-piece sling 9' x 40' long 22 oz vinyl/polyester sling capable of storing one 45' x 45' wrestling/gymnastics mat and one (1) bottom one-piece 18' x 40' long 22 oz. vinyl/polyester super sling, capable of storing two (2) 45' x 45' wrestling/gymnastic mats rolled inside one another. Storage system unit shall be complete with (three) forked end 5/16" x 35' support aircraft cables and all hardware required for installation and operation. Storage system shall be installed with a minimum four clamped support points spaced equally on architect/structural engineer approved ceiling truss or wall.
 - **B. HOISTING**: Vertical hoisting shall be motor operated, 3 H.P. 208, 230 or 460 volts three phase complete with up/down limit switches, 29.5 lb fast action brake motor and 95% efficiency gearing. Final output speed is 15-rpm 12,510lb inch torque output to lift approximately 6000 pounds of mat on three 4" diameter drums directly coupled to a 2" diameter x 20' long solid keyed shaft. Motor and starter shall have thermal overload protection and motor shall be factory lubricated and sealed. System shall be pre-wired with a furnished electrical key switch with automatic off return and raise/lower legend plate, plus an emergency lowering manual override brake, in case of a power outage.
 - **C. TESTING**: Mat storage system must show documented **proof** from an independent testing laboratory that load tests were performed on entire system and clamps to 17,500 lbs. Tested system must not have outside assisting devices such as load-bar pulleys, chain hoists, larger motors, or a sprocket/roller chain between reducer and shaft. System shall be direct helical gear drive only.
 - **D.** Manufacturer must show **proof** that they have manufactured mat hoisting systems for at least fifteen years to offer **15-year** warranty.

3.0 PREPARATION

- A. Coordinate electrical rough-in requirements and locations with the electrician.
- B. Installation shall be coordinated through the General Contractor on new construction.

3.1 INSTALLATION

- A. Deliver and install Mat Hoist® storage system at location indicated on plans.
- **B.** Electrical Contractor shall furnish and install electrical raceways, boxes, wiring, safety disconnect switch, and make final connections to manufacturer furnished starter, up/down limit switches and keyed control switch. Contractor shall also verify Mat Hoist® is operating in correct rotation with up/down limit switches.
- **C.** Adjust storage unit to correct height, level and alignment.
- **D.** In addition to these specifications, the entire Mat Hoist® installation shall be in accordance with the manufacturer's installation procedures.
- **E.** Installer instructs owner/general contractor in the operation of the storage system.