



Illustrates: Suspension perpendicular to truss system.  
 Added steel bolted perpendicular onto 2 or more truss.  
 ST-1 then bolted to added steel and embedded into wall.

Note: ST-1 all thread rod  
 and wall prep are additional  
 costs.

Note: Structural Strength of Truss & Wall NDT Responsibility of Mat Hoisto Manufacturer.

NGE Inc. P.O. Box 370/Industrial Park 302 North Erickson Roland, IA 50236	Mat Hoisto 500  Drawing MH500-20	Phone: (515)-388-4118 Fax: (515) 388-4340 Email: mathoist@mathoist.com Website: www.mathoist.com
--	--	---